BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

BBMP/2023-24/OW/WORK_INDENT2002

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/10/2023-24 Dated: 03-02-2024

APPROVED TENDER SCHEDULE - B

Item-13

Name of Work:-Construction of RO Plant and other development works at JPN colony census block No 89/1, 89/2 in chowdeshwari ward no 02 of Yelahanka sub division

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.AKSHAY KUMAR H B(AKSHAY CONSTRUCTIONS)	
				Rate	Rate in words
1	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. Depth exceeding 1.5m, but not exceeding 3 m	Cum	130.19	225.45	Two Hundred TwentyFive Paise FourtyFive Only
2	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates.Specification	Cum	4.95	6516.38	Six Thousand Five Hundred Sixteen Paise ThirtyEight Only
3	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	6.59	7238.03	Seven Thousand Two Hundred ThirtyEight Paise Three Only
4	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) Mix 1:2:4 (M15) Using 20 mm nominal size graded crushed coarse aggregates	Cum	0.88	6906.10	Six Thousand Nine Hundred Six Paise Ten Only
5	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations and other similar works etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	115.49	181.26	One Hundred EightyOne Paise TwentySix Only
6	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 14 m3)	Cum	245.69	97.43	NinetySeven Paise FourtyThree Only

Akshay

Scanned with OKEN Scanner

	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.AKSHAY KUMAR H B(AKSHAY CONSTRUCTIONS)	
				Rate	Rate in words
7	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km .	T.Km	314.48	121.12	One Hundred TwentyOne Paise Twelve Only
8	Providing and constructing laterite size stone masonry including cost and conveyance of all material curing etc complete as per specification IS 3620/1979 having compressive strength not less than 3.5N/mm2 for saturated dry samples- for super structure in CM 1:6	Cum	1.17	4482.85	Four Thousand Four Hundred EightyTwo Paise EightyFive Only
9	Providing Flush/ Ruled pointing: Pointing on stone work with cementmortar 1:3 (1 cement : 3 fine sand) after raking joints to depth nicely lining, including cost of materials, labour, curing as per specifications and as per directions of Engineer-in-charge.	Sqm	2.60	288.89	Two Hundred EightyEight Paise EightyNine Only
10	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/ trap/ basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates.	Cum	10.69	7706.96	Seven Thousand Seven Hundred Six Paise NinetySix Only
11	Providing and laying in position Reinforced cement concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/ trap/ basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately) M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates -Column's	Cum	1.0100	8090.19	Eight Thousand Ninety Paise Nineteen Only
12	Providing and laying in position Reinforced cement concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/ trap/ basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately) M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates -Lintel	Cum	0.52	8825.67	Eight Thousand Eight Hundred TwentyFive Paise SixtySeven Only

Akshay

Scanned with OKEN Scanner

	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.AKSHAY KUMAR H B(AKSHAY CONSTRUCTIONS)	
				Rate	Rate in words
13	Providing and laying in position Reinforced cement concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/ trap/ basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately) M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates - Roof Slab	Cum	1.61	8825.67	Eight Thousand Eight Hundred TwentyFive Paise SixtySeven Only
14	Providing and laying in position Reinforced cement concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/ trap/ basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately) M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates Beam	Cum	0.78	8825.67	Eight Thousand Eight Hundred TwentyFive Paise SixtySeven Only
15	Providing and laying in position plain cement concrete for levellingcourse for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately)Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregates	Cum	1.38	6713.51	Six Thousand Seven Hundred Thirteen Paise FiftyOne Only
16	Providing Thermo-Mechanically Treated bars of grade Fe-550 Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position, binding and anchoring to adjacent members whereever necessary complete as per Design including cost of material, labour, usage charges complete as per specifications. (The laps and wastages shall not be measured separately)	Kg	1751.00	108.76	One Hundred Eight Paise SeventySix Only
17	Providing and constructing load bearing wall with solid concrete blocks of size 400X200X200mm having block density not less than 1800kg/m3 having a minimum average compressive strength 5.00N/mm2 confirming to IS 2185 (part 1) :2005 and constructed with cement mortar 1:4,as per IS 2572:2005 including cost of materials, labour charges, scaffolding, curing, hire charges of machinaries etc., complete as per specifications.	Sqm	35.46	1484.09	One Thousand Four Hundred EightyFour Paise Nine Only
18	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	Sqm	8.28	1394.59	One Thousand Three Hundred NinetyFour Paise FiftyNine Only

Akshay

Scanned with OKEN Scanner

	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.AKSHAY KUMAR H B(AKSHAY CONSTRUCTIONS)	
				Rate	Rate in words
19	Providing 18 mm cement plaster in two coats under layer 12 mm thick cement plaster with cement mortar 1:5 (1 cement : 5 coarse sand) and a top layer 6 mm thick cement plaster with cement mortar 1:3 (1 cement: 3 coarse sand) finished rough with sponge to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	60.90	436.16	Four Hundred ThirtySix Paise Sixteen Only
20	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	41.28	365.92	Three Hundred SixtyFive Paise NinetyTwo Only
21	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per specifications and as per directions of Engineer in charge.	Sqm	41.28	113.29	One Hundred Thirteen Paise TwentyNine Only
22	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two coats on new work after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	41.28	130.28	One Hundred Thirty Paise TwentyEight Only
23	Providing external walls with texture finish using approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading and unloading, all lead and lift and all other incidental charges including scaffolding and removing stains, complete as per specifications.	Sqm	52.80	201.65	Two Hundred One Paise SixtyFive Only
24	Providing and laying 52 mm thick cement concrete flooring with concrete hardener topping, under layer 40 mm thick cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) and top layer 12 mm thick cement hardener consisting of mix 1:2 (1 cement hardener mix : 2 graded stone aggregate 6 mm nominal size) by volume, hardening compound mixed @ 2 litre per 50 kg of cement or as per direction of Engineer incharge.	Sqm	9.00	906.31	Nine Hundred Six Paise ThirtyOne Only
25	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per m2 including pointing in white cement mixed with pigment of matching shade complete.	Sqm	9.00	1252.98	One Thousand Two Hundred FiftyTwo Paise NinetyEight Only
26	Providing skirting, dadooing, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.	Sqm	22.14	1641.56	One Thousand Six Hundred FourtyOne Paise FiftySix Only
27	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings / wooden frames with rawl plugs screws etc.	Kg	11.34	207.32	Two Hundred Seven Paise ThirtyTwo Only

Akshay

Scanned with OKEN Scanner

	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.AKSHAY KUMAR H B(AKSHAY CONSTRUCTIONS)	
				Rate	Rate in words
28	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two coat applied @ 0.90 ltr/10 m² over an under coat of primer applied @ 0.80 ltr/10 m² of approved brand and manufacture including preparing the surface after thorougly cleaning oil, grease, dirt and foreign matter, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	0.54	157.47	One Hundred FiftySeven Paise FourtySeven Only
29	PProviding & fixing of 3 track x 2 panel sliding windows made out of multi chambered UPVC Matching to RAL 9016 sections and with minimum Ti O2 Titanium Dioxide at 6PHR with TPE Thermo Plastic Elastomer and lead free, gaskets grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame having an overall size of 108mm width x 45mm height with reinforcement of 1mm thickness and Sash with overall size of 39mm x 75mm with GI reinforcement of 2mm and mesh sash of size 37mm x 58mm. Coextruded Glazing bead for fixing of glass shall be of size 20mm x 24 mm. Windows shall be provided with 6mm plain float glass, standard hardware & Multi point locking system with touch lock. Wall thickness of frame & sash shall be of 2mm 2.5mm. Maximum possible size 2419mm x 2200mm. The cost is inclusive of all fixtures and separate charges for minor T&Ps shall not be made	Sqm	4.32	7628.88	Seven Thousand Six Hundred TwentyEight Paise EightyEight Only
30	Construction of Embankment by excavating the available approved Gravel/Murrum deposited at a place or borrow pits during or prior excavation with all lifts and lead, transportation to site, spreading, grading to required slope and compacting to meet the requirement complete as per specifications, including cost of labour,rolling,water,all materials,usage& all other appurtenaces required to complete the work..	Cum	2.70	455.42	Four Hundred FiftyFive Paise FourtyTwo Only
31	Providing and laying water proofing treatment to the Water tanks & Liquid Retaining structures with two component acrylic polymer modified cementitious waterproofing membrane with minimum elongation of 50% applied @ 1.5 kg/m2 for internal side waterproofing in two layers with waiting period of 4-6 hrs per layer and food grade epoxy coating in two coats certified by CFTRI Mysuru, including surface preparation completely as per specification & with a 10 years warranty on product & work from certified manufacturers as per the direction of the Engineer In charge.	Sqm	9.00	574.38	Five Hundred SeventyFour Paise ThirtyEight Only
32	Providing and fixing on wall face unplasticised rigid PVC rain water pipes conforming to IS:13592 Type A, including jointing with seal ring conforming to IS:5382, leaving 10mm gap for thermal expansion, [i] single socketed pipes 100mm diameter.	Mtr	6.00	329.67	Three Hundred TwentyNine Paise SixtySeven Only
33	Providing and laying water proofing treatment to the Water tanks & Liquid Retaining structures with two component acrylic polymer modified cementitious waterproofing membrane with minimum elongation of 50% applied @ 1.5 kg/m2 for internal side waterproofing in two layers with waiting period of 4-6 hrs per layer and food grade epoxy coating in two coats certified by CFTRI Mysuru, including surface preparation completely as per specification & with a 10 years warranty on product & work from certified manufacturers as per the direction of the Engineer In charge.	Sqm	27.18	574.38	Five Hundred SeventyFour Paise ThirtyEight Only

Akshay

Scanned with OKEN Scanner

	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.AKSHAY KUMAR H B(AKSHAY CONSTRUCTIONS)	
				Rate	Rate in words
34	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters. 80x0.90 mm M.S. laths with 0.90 mm thick top cover including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	Sqm	3.78	2982.90	Two Thousand Nine Hundred EightyTwo Paise Ninety Only
35	Providing and placing on terrace(at all floor levels), polyethylene water storage tanks as per IS 12701 marked,with cover and suitable locking arrangement and making necessary holes for inlet,outlet and overflow pipes but without fittings and the base support for tank(For 1000 litre capacity)	Ltr	2000.00	10.20	Ten Paise Twenty Only
36	Supplying and installation of 2000 LPH RO drinking water treatment plant comprising of raw water strorage tank,anti rolling closing system with pump & tank sand filler activated carbon filter,High pressure pump,R.O membranes,R.O.Pressure Tubes, Skid house the complete R.O plant,control panel,Chemical cleaning tank,Ph dosing system with pump and dosing tank product water storage UV Sterilizer Interconnecting piping with SKID,complete instrumentation with necessary gauges and flow indicator as required in the plant with PH meter etc.	Nos	1.00	1081395.00	Ten Lakh EightyOne Thousand Three Hundred NinetyFive Only
37	PTMT grating 100 mm dia.	Each	3.00	18.13	Eighteen Paise Thirteen Only
38	Providing and fixing brass bib cock of approved quality : 20 mm nominal bore.	Nos	4.00	345.53	Three Hundred FourtyFive Paise FiftyThree Only
39	Providing and fixing brass stop cock of approved quality : 20 mm nominal bore	Nos	4.00	345.53	Three Hundred FourtyFive Paise FiftyThree Only
40	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete : 20 mm nominal bore	Nos	6.00	355.73	Three Hundred FiftyFive Paise SeventyThree Only
41	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.,) 20mm nominal dia pipes	Mtr	24.00	429.37	Four Hundred TwentyNine Paise ThirtySeven Only
42	Providing and fixing on wall face unplasticised rigid PVC rain water pipes conforming to IS:13592 Type A, including jointing with seal ring conforming to IS:5382, leaving 10mm gap for thermal expansion, [i] single socketed pipes 100mm diameter	Mtr	6.00	329.67	Three Hundred TwentyNine Paise SixtySeven Only
43	Supply and delivery of Centrifugal pumpset at site brand new best make and with discharge duty confirming to ISI standards and its latest amendments2 HP, Size 50x40 Head 22M, Discharge 186 LPM	Each	1.00	19791.59	Nineteen Thousand Seven Hundred NinetyOne Paise FiftyNine Only

Akshay

Scanned with OKEN Scanner

	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.AKSHAY KUMAR H B(AKSHAY CONSTRUCTIONS)	
				Rate	Rate in words
44	Open conduit System: Supplying heavy gauge PVC conduit pipe .....dia confirming to IS 2509 with suitable size bends, plugs in case of RCC ceiling and RCC wall stone structure or rawl plugs in case of brick walls and cement plastering damaged portion using heavy gauge saddles at an interval of 700mm using WF screws.a) 19/20mm dia 2mm thick	Mtr	145.00	71.06	SeventyOne Paise Six Only
45	Supplying and flush mounting teak wooden box without front plank, made of not less than 15mm thick wood, after due groove cutting, necessary masonry patch work complete. d)8''x6''x3''(203x152x76mm)	Each	2.00	88.57	EightyEight Paise FiftySeven Only
46	Point wiring using copper wire with switch Supplying and wiring adopting loop system in existing PVC Conduit/casing caping using Copper PVC insulated multi strand 2x1.5Sqmm copper wire with a 6Amps flush type SP control switch shall be fixied on the exisiting plastic sheet /gang box, the pther end of the wires shall be terminated with sufficient loose length in a wood/PVC round block.complete for each outlet. I. Point wiring using class A materials a) Short point upto 3Mtr from tapping point to out let via switch	Point	2.00	293.52	Two Hundred NinetyThree Paise FiftyTwo Only
47	Point wiring using copper wire with switch Supplying and wiring adopting loop system in existing PVC Conduit/casing caping using Copper PVC insulated multi strand 2x1.5Sqmm copper wire with a 6Amps flush type SP control switch shall be fixied on the exisiting plastic sheet /gang box, the pther end of the wires shall be terminated with sufficient loose length in a wood/PVC round block.complete for each outlet. I. Point wiring using class A materials b) Medium point above 3Mtr upto 6Mtr from tapping pointr to out let via switch.	Each	2.00	405.78	Four Hundred Five Paise SeventyEight Only
48	Point wiring using copper wire with switch Supplying and wiring adopting loop system in existing PVC Conduit/casing caping using Copper PVC insulated multi strand 2x1.5Sqmm copper wire with a 6Amps flush type SP control switch shall be fixied on the exisiting plastic sheet /gang box, the pther end of the wires shall be terminated with sufficient loose length in a wood/PVC round block.complete for each outlet. I. Point wiring using class A materialsc)Long point above 6Mtr upto 10Mtr from tapping point to out let via switch.	Each	6.00	587.04	Five Hundred EightySeven Paise Four Only
49	Supplying 6A flush/projected type socket and a 6 amps flush/ projected type SP switch either surface/flush mounting in a exisiting gang box or in a 4mm thick plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wires as required. b) 6Amps 3/5 way	Each	1.00	151.40	One Hundred FiftyOne Paise Fourty Only
50	Wiring for lighting/power circuit using one of FLRS PVC insulated 1100v grade, multis and CopperWITH LOW conductor single core cable in open or consealed system of wiring.I Group A Materials.a) 1.5 sqmm	Mtr	125.00	26.78	TwentySix Paise SeventyEight Only
51	Wiring for lighting/power circuit using one of FLRS PVC insulated 1100v grade, multis and CopperWITH LOW conductor single core cable in open or consealed system of wiring.I Group A Materials.b)2.5Sqmm	Mtr	120.00	43.26	FourtyThree Paise TwentySix Only
52	Wiring for lighting/power circuit using one of FLRS PVC insulated 1100v grade, multis and CopperWITH LOW conductor single core cable in open or consealed system of wiring.I Group A Materials.c) 4 sqmm	Mtr	135.00	64.88	SixtyFour Paise EightyEight Only
53	Supplying 4mm thick plastic sheet with necessary niches for fixing switches, regulators etc., and fixing on exisiting wood or metal box using N.F.screws	Sqm	1500.00	0.42	Paise FourtyTwo Only

Scanned with OKEN Scanner

	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.AKSHAY KUMAR H B(AKSHAY CONSTRUCTIONS)	
				Rate	Rate in words
54	Supplying and fixing retrofit type -PL-LED lamp LED linear Source with CCT 6500 degree K CR 170efficacy 80 lumen per watt,life 25000 burning hours and compliance to IS 10322 IEC 60598 LM 79 and LM80 The LED are driven by HF electronicdriver integrated in the system, with PF 0.95 power loss Should 5 of lam Wattage short Circuit and open circuit Protection to be integrated Circuit THD less than 20% life as per LM79. the operating input voltage should be between130 t 275 volts. Tested by NABL CPRI accredited laboratory with 2 years Warranty agnist any manufacturing defect working under standard electrical condition.18-20Watts	Each	6.00	722.99	Seven Hundred TwentyTwo Paise NinetyNine Only
55	Supplying and fixing of T5 Fluorescent Tube with 14W power consumption with low 3mg Mercury content & below 40% glass content than T8 lamp & 20% less phosphor coating than T8 with initial lumen on 1350 (for 3000-6500 deg Kelvin), rated Avg life (12 Hr. Cycle) of greater than 35000 burring hours. Operating voltage range from 180V to 265V, 50Hz AC power Supply, 14 W Lamp	Each	4.00	145.22	One Hundred FourtyFive Paise TwentyTwo Only
56	Supply and fixing polished wood board made of not less than 15mm thick plank on both sides with plank made out of not more than 2 pices and fixing the same to the wall using tapered inverted woode plug screws etc., a) 20"x20"2.5"	Each	4.00	335.88	Three Hundred ThirtyFive Paise EightyEight Only
57	Supplying and fixing of Procelain fuse channel with cut out on exisiting wooden/panel using necessary nuts, bolts and washers etc., complete.a) 32Amps	Each	6.00	248.21	Two Hundred FourtyEight Paise TwentyOne Only
58	Supply of an load charge over switches 4poles 415v 50Hz A.C supply with AC23A duty a) up to 63amps Groups A (PWD Electrical SR 2023-24 PART III PgNo 15.Item No 5.11.1)	Each	1.00	5643.85	Five Thousand Six Hundred FourtyThree Paise EightyFive Only
59	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and C type curve indicator ON/OFF Energy cross 3 with short circuit breaking capacity of 10K and complete wiring as required. 40 A TPN . Group A	Each	1.00	3135.02	Three Thousand One Hundred ThirtyFive Paise Two Only
60	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and C type curve indicator ON/OFF Energy cross 3 with short circuit breaking capacity of 10K and complete wiring as required. 6-32amps TPN Group A	Each	1.00	1768.34	One Thousand Seven Hundred SixtyEight Paise ThirtyFour Only
61	Supplying, fixing and wiring Electronic Trivector Meter (ETV) 5 to 32/63 A three phase 4 wire whole current class-1 Accuracy Energy Meter.	Each	1.00	5875.58	Five Thousand Eight Hundred SeventyFive Paise FiftyEight Only
62	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipments on the meter board using 40mm dia 2.90 thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proprotion of salt and charcoal 150mm alround the pipe to complete depth. the connection form the pipe to the conduit etc, is to be established through GI wire of size as oer ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and checknuts etc, the pipe shall have 16 through holes of 12mm dia.	Nos	1.00	3614.95	Three Thousand Six Hundred Fourteen Paise NinetyFive Only
63	Supplying and running of GI/Copper strips for grounding connections using necessary fixing material as required GI strip 25x3mm	Mtr	20.00	84.45	EightyFour Paise FourtyFive Only

Scanned with OKEN Scanner

	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.AKSHAY KUMAR H B(AKSHAY CONSTRUCTIONS)	
				Rate	Rate in words
64	Supplying and fixing of class A (medium duty) Gl pipe of wall thick ness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class. a) 40mm	Mtr	4.00	345.02	Three Hundred FourtyFive Paise Two Only
65	Supplying and running of GI/Copper strips for grounding connections using necessary fixing material as required GI strip 25x3mm	Mtr	25.00	77.24	SeventySeven Paise TwentyFour Only
66	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanished, steel wire/steel tap armoured cable with PVC outer sheating 1.1 KV class.I. Class 'A' PVC Cable.d) 4 core 16 sqmm	Mtr	20.00	154.49	One Hundred FiftyFour Paise FourtyNine Only
67	Labour charges for lying of 1.1 KV class UG cable when supplied agency in existing trench Gl pipe / stoneware pipe / on wall /on pole as required. I. In existing trench/duct.a) 6 sqmm to 16 sqmm	Mtr	20.00	12.24	Twelve Paise TwentyFour Only
68	Digging of trench of 0.6 m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc.,complete. .a) In soil (ordinary)	Mtr	25.00	78.27	SeventyEight Paise TwentySeven Only
69	Supplying &fixing L.T.cast iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers ect.b) 16 Sqmm	Each	6.00	278.07	Two Hundred SeventyEight Paise Seven Only
70	Providing and fixing Precast RCC Slabs 100mm Thick as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	99.36	2133.95	Two Thousand One Hundred ThirtyThree Paise NinetyFive Only

Akshay

Signature of the Contractor

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagar
BANGALORE - 560064

Scanned with OKEN Scanner